

HOEDSPRUIT SIDEWALK

ITEM NO	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
		<u>SEGMENTAL BLOCK PAVING FOR SIDEWALKS</u>				
SABS1200A		<u>GENERAL</u>				
		Site Establishment	sum	1,00		
		Contractual requirements	sum	1,00		
		Removal of site Establishment	sum	1,00		
		Provision for Health and Safety requirements. (provision of PPE's for labours)	sum	1,00		
		Removing existing paving block, sorting them according to usability and quality and stockpile them to be re-used.	m²	2100,00		
		<u>EARTHWORKS</u>				
		Rip and compact existing layer to a minimum depth of 150mm.	m³	540,00		
		Import 150mm of topsoil from commercial source and compact to 95% MOD AASTHO	m³	540,00		
51,04	LI	Concrete Block Paving				
		a) Provide and construct SABS approved grey and marron segmented paving lain in Herringbone pattern 60mm thick, 25 Mpa Type S-A concrete paving blocks. Price must include bedding, sand layer, compaction and finishing.	m²	5 600,00		
	LI	KERBING				
		a) 1000 length x 75mm wide x 150mm deep cast insitu concrete class 30/19	m	2000,00		
		a) 1000 length x 100mm wide x 250mm deep cast insitu concrete class 30/19	m	4,50		
51,05	LI	Cast insitu concrete edge and immediate beams				
		a) 150mm wide x 300mm deep cast insitu concrete class 25/19 with class U2 finish	m³	25,00		
		<u>FINISHING OF WORKS</u>				
		Cleaing and clearing of unwated materials on the walkways.	Sum	1,00		

SUB-TOTAL	
10% Contingencies	
SUB-TOTAL	
15% VAT	
TOTAL	