

CONTRACT NO. : MLM/SCM/42/2022

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
1.00	<u>PRELIMINARY AND GENERAL</u>				
1(a)	Site Establishment	sum	1		
1(b)	Contractual requirements	sum	1		
1©	Removal of site Establishment	sum	1		
1(d)	OHSA Requirements	sum	1		
2.00	<u>Site Clearance (FENCE LINE)</u>				
2.10	Clear and Grub 2.0m wide strip along the fence line	m	650,00		
2.20	Remove and grub large trees and tree stumps of girth				
	a. Over 1m up to and including 2m	No	12,00		
	b. Over 2m up to including 3m	No	9,00		
3.00	<u>EARTHWORKS (Small works) SABS 1200 DA</u>				
3.10	Excavate in all materials for posts				
	a. Up to 1m depth	m ³	20,00		
4.00	<u>POSTS</u>				
4.10	Supply and install posts excl. excavation and concrete	No	71,00		
	a. Corner posts : 102mm dia, 2.8mm wall thickness, galvanized , 2400mm long with cap and base Plate(installed in 20m spacings)	No	28,00		
	b. Stays : 76mm dia 3.0mm wall thickness, galvanized, 1800mm long	No	2,00		
	c. Gate posts : 102mm dia. 2.8mm wall thickness, galvanized , 2400mm long with cap and base Plate	No	284,00		
	d. Standards: 2.5kg/m bitumen dipped Y steel section, 2400mm long Rammed 600mm into Ground at 5m spacings	No			
4.20	Smooth wire 4,8mm thick and fully galvanized.				
	a. Barbed wire: high tensile grade, single stranded 3.15 x 2.5 mm oval shaped wire, with a 2.81 mm equivalent diameter and fully galvanized.	m	3 500,00		
5.00	<u>GATES</u>				
5.10	Roll steel gate 3.5m wide made of square tubings and angle irons	No	2,00		
6.00	<u>CONCRETE FOR POSTS</u>				
6.10	15Mpa / 19mm Concrete backfill for posts	m ³	6,00		
6.20	Diamond mesh Install diamond mesh 2.5mm x 63mm x 1800mm high	m	500,00		
Total Carried Forward					

CONTRACT NO. : MLM/SCM/42/2022

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
Brought Forward					
7,00	VIP TOILETS: Ventilated Pit Latrine with a lined pit and superstructure constructed from corrugated iron sheets and toilet seat. There should also be an installation of ventilation pipe on back floor slab. Refer to Drawing No:	No	2,00		
Total Carried Forward To Summary					

CONTRACT NO. : MLM/SCM/42/2022

CONTRACT NO. : MLM/SCM/42 /2022

DESCRIPTION	AMOUNT
SUMMARY TO THE FENCING BOQ	
SUB- TOTAL	
VAT	
TOTAL (THE TOTAL AMOUNT BE TAKEN TO FORM OF OFFER)	